

# **HILLSBORO R-III SCHOOL DISTRICT REQUEST FOR PROPOSAL Elementary Kitchen Pipe Replacement**

RETURN PROPOSAL NO LATER THAN: 2:00 p.m. C.S.T.,  
Monday, June 17, 2019

RETURN PROPOSAL AND ADDENDA TO:

Hillsboro R-III School District

ATTN: Ray Bess - Director of Buildings and Grounds  
#5 Ridgewood Drive, Hillsboro, Missouri 63050

## **Request for Proposal Specifications**

Call for an appointment to review the area of the project -  
636.789.0000 Ext. 3501

### **Project Overview:**

- Remove about 100' old cast iron from under the floor
- The contractor will move tables, dishwasher, other equipment to do work
- The contractor will put tables, dishwasher, other equipment back in place
- Schedule 40 PVC will be used, plus "Y" or elbows needed
- Backfill with  $\frac{3}{4}$ " to 1" clean gravel
- Repatch floor to the proper height to get VCT reset by the school district
- Room plastic to maintain dust
- The contractor will clean up all left-over materials before leaving
- Completion Date: July 17, 2019