

Town of Danville

Peacham Rd. Shared-Use Path & Hill St. Sidewalk



Conceptual Design Review Meeting

September 25th, 2024 6:30 PM

Agenda



Introductions



Project Purpose & Need



Review of Scope & Schedule



Project Area Overview



Preferred Alternative / Conceptual Plans



General Questions and/or Comments



Next Steps

Project Steering Committee

- Ken Robie, PE | DuBoise & King, Municipal Project Manager
- Chris Hunt | VTrans, Project Manager
- Michelle Leclerc | Danville Town Clerk & Treasurer
- Janice Ouellette | Danville Selectboard Chair
- Allison Low | Danville Selectboard Member
- Laural Ruggles | Danville Village to Village Committee
- Keith Gadapee | Danville Road Foreman
- Audrey DeProspero | Danville Selectboard Assistant

VHB Project Team

- Branden Roberts, PE | VHB Project Manager
- Evan Detrick, PE | VHB Quality Control
- Tanner Burt, PE | VHB Transportation Engineer



Previously Identified Project Purpose & Need

The **Purpose** and **Need** of the **Peacham Road Shared-Use Path and Hill Street Sidewalk** as noted in the Bicycle & Pedestrian Pathway Scoping Study prepared for the town in 2014:

The purpose of the project is to create a safe route for recreational users from the intersection of Hill Street and Highland Avenue to the Danville recreational fields located off Peacham Road and to bring users of the Lamoille Valley Rail Trail into Danville Village.

The need for the project is to improve and expand safe routes for recreational user in the town of Danville.

Scope and Schedule

- ✓ Project Kickoff Meeting
- ✓ Base Mapping/Existing Conditions
- **✓ Develop Conceptual Plans**
- Conceptual Design Review Meeting
- NEPA Documentation
- NEPA Review
- Preliminary Plans
- Permitting and Right-of-Way Plans
- Final Plans
- Contract Plans/Bid Package
- Construction

May 2025

May – June 2025

June – August 2025

Today

September 2025

September 2025 – February 2026

January – March 2026

May 2026 - March 2027

April – June 2027

July – August 2027

2028





Project Area






Conceptual Plan Layout








Peacham Road Shared-Use-Path Layout






Peacham Road Rendering




Shared-Use Path Example: Colchester, VT







Typical Path Section




PEACHAM RD - SHARED USE PATH - CUT CONDITION

(N.T.S.)



Typical Path Section








Peacham Road - LVRT Intersection






Lamoille Valley Rail Trail Intersection



Peacham Road – Fire Department





Fire Department Driveway and Drainage



Peacham Road - Danville Place






Danville Place





Danville Place – Alternative Drive






Peacham Road - School Access






School Access




Peacham Road - End of Shared-Use Path





End of Shared-Use-Path to Danville Green




Hill Street Sidewalk Layout






Typical Sidewalk & Paving






Typical Sidewalk Section





Typical Sidewalk & Curb Section






Hill Street - Parking Improvements






Hill Street Parking Improvements



Streetscape






Hill Street - Sidewalk and Curb





Hill Street - Sidewalk and Curb



Cost Estimate

2014 Bicycle and Pedestrian Pathway Scoping Study Estimate

Peacham Road Shared-Use Path

Construction Cost		\$288,000
Engineering	Design Phase Engineering	\$69,000
	Construction Phase Engineering	\$69,000
Local Project Management		\$37,000
Legal and Fiscal		\$10,000
Total Shared-Use-Path Cost		\$473,000

Hill Street Sidewalk (Highland Ave. to Hill St. Business Block)

Construction Cost		\$210,000
Engineering	Design Phase Engineering	\$43,000
	Construction Phase Engineering	\$43,000
Local Project Management		\$23,000
Legal and Fiscal		\$10,000
Total Sidewalk Cost		\$329,000

Hill Street Business Block Sidewalk

Construction Cost		\$44,000
Engineering	Design Phase Engineering	\$10,000
	Construction Phase Engineering	\$10,000
Local Project Management		\$6,000
Legal and Fiscal		\$1,000
Total Business Bock Sidewalk Cost		\$71,000

Total Project Cost: \$873,000*

*2017 projected estimate



Cost Estimate

Conceptual Construction Cost:

Total	\$1,264,640
Mobilization (10%)	\$107,173
Traffic Control (8%)	\$85,738
Contingency (25%)	\$214,346
Hill Street Sidewalk – Grand View Ave. to Highland Ave.	\$203,032
Hill Street Sidewalk – Business District to Grand View Ave.	\$89,400
Hill Street Parking Reconfiguration	\$86,806
Peacham Road Shared-Use Path	\$478,145



Next Steps

- NEPA Documentation
- NEPA Review
- Preliminary Plans
- Permitting & Right-of-Way
- Final Plans
- Contract Plans/Bid Package
- Construction

September 2025 – February 2026

February 2026

March 2026

March 2027

June 2027

August 2027

2028



Questions and Comment



From collection Eastern Illustrating & Publishing Company Collection



Stay Connected!



Branden Roberts, VHB Project Manager

broberts@vhb.com

802.497.6193



Tanner Burt, VHB Transportation Engineer

tburt@vhb.com

802.391.5571



Ken Robie, Municipal Project Manager

krobie@dubois-king.com

802.370.6126