



① Level 3
1/4" = 1'-0"

Demolition notes

- Retain ceiling tiles and grid for attic stock.
- Retain existing light fixtures for reuse.
- Remove mechanized projection screen.
- Consult a licensed fire protection engineer or licensed fire sprinkler contractor for sprinkler revisions.
- Remove speakers from ceiling.
- Remove all floor boxes.
- Protect existing finishes to remain during construction.
- Refinish walls after construction with like paint.

New construction notes

- New partitions are 3 5/8" metal stud with 5/8" type X fire resistant gypsum board each side (4 7/8" total width), with Certainteed Acoustatherm 3 1/2" batts installed floor to ceiling. New partitions are to be built to the underside of the structure above. Seal top of partitions to structure with silicone or construction adhesive for acoustic performance.
- New rubber base to match existing.
- Dimensions are from face of assembly to face of assembly, unless noted otherwise.

Doors

Doors, frames, and hardware are to match the existing entry door in all characteristics, except no closers and no glazed sidelites or transoms are required. Hardware to have office function locks.

Flooring

- Maintain existing carpet in place in Reception. Repair with like tiles where damaged during construction.
- New carpet with border in Office.
- VCT in bathroom: Armstrong Imperial Texture Standard Excelon, 57504 Chocolate.

Project number . . .
Date . . .