PUBLIC MEETING MAP

PROJECT 48544 (R-5927)

MOORE COUNTY

US 15/501 FROM THE TRAFFIC CIRCLE IN PINEHURST TO NC 73. WIDEN TO MULTILANES.

ROLL 2 OF 2

09/2026

NOTE: The Best-Fit Alignment and West Widening Alternates are the same for most of the project. The two alternates differ from SR 1844 (Campground Road) to north of SR 1285 (Lea Road). The Best-Fit Alignment Alternate is shown on the inset on Roll 2, while the main part of Roll 2 shows the West Widening Alternate.

DESIGN DATA - NC 73

Functional Class.	=	Collector
Design Speed	=	60 MPH
Max. Superelev.	=	0.06

DESIGN DATA - US 15/501 FROM NC 73 TO SR 1838 (JUNIPER LAKE RD).

Functional Class.	=	Arterial
Design Speed	=	60 MPH
Max. Superelev.	=	0.04

TRAFFIC VOLUME DATA — MCDANIEL ROAD / NC 73

525		525				
525		525				
14,025	100	14,125	6,950	6,975		
19,075	150	19,225	9,475	9,600	13,000	
					17,400	
US-15/501		US-15/501			US-15/501	
	0.4%					
	0.8%					

2031 AADT
2051 AADT

TRAFFIC VOLUME DATA — LEA ROAD

525		525		
525		525		
14,025	475	14,500		
19,075	725	19,800		
US-15/501		US-15/501		

2031 AADT
2051 AADT

ORTHOPHOTOGRAPHY DATA
Source: NCDOT Photogrammetry
Year: 2020

INCOMPLETE PLANS FOR PRELIMINARY PLANS

100' 0' 100' 200'
(ENGLISH)





MATCH LINE SHEET 1 -L3- STA. 102+00.00



INSET – BEST-FIT ALIGNMENT ALTERNATE



LEGEND

- BUILDINGS
- EXISTING RIGHT OF WAY
- PROPOSED RIGHT OF WAY
- PROPOSED EASEMENTS (DRAINAGE, CONSTRUCTION, ETC.)
- EXISTING ROADWAY
- EXISTING ROADWAY TO BE REMOVED
- EXISTING ROADWAY TO BE RESURFACED
- PROPOSED ROADWAY
- FUTURE ROADWAY
- PROPOSED STRUCTURES, ISLAND, CURB AND GUTTER
- EXISTING STRUCTURES, ISLAND, CURB AND GUTTER TO BE RETAINED
- EXISTING STRUCTURES, ISLAND, CURB AND GUTTER TO BE REMOVED
- LAKES, RIVER, STREAMS AND PONDS
- WETLAND
- EXISTING EASEMENTS
- PROPOSED CONTROL OF ACCESS
- PROPOSED PARTIAL CONTROL OF ACCESS
- PARKING AREA
- FUTURE ADT
- PROPERTY LINES
- EXISTING TRAFFIC SIGNAL TO BE REMOVED
- PROPOSED TRAFFIC SIGNAL

NOTE:
To provide greater visual clarity existing and proposed utilities are not shown on these maps or on other displays. The utility information shown on these maps is limited to locations of major existing or potential utility easements. The designs shown on these maps, including utility easements, are preliminary and are subject to change.

NOTE:
The limits of construction and their impacts shown on this meeting map are based on preliminary designs and survey information. During the final design stage efforts to minimize impacts, where feasible, will be made using final survey information. Driveway locations will also be determined during final design.

NOTE:
Partial Control of Access is defined as connections to a facility provided via ramps at interchanges, at-grade intersections, and private driveways. Private driveway connections are normally defined as a maximum of one connection per parcel. One connection is defined as one ingress and one egress point.

NOTE:
Full Control of Access is defined as connections to a facility provided only via ramps at interchanges. All cross-streets are grade-separated. No private driveway connections are allowed.

PUBLIC MEETING MAP
PROJECT 48544 (R-5927)
MOORE COUNTY
US 15/501 FROM THE TRAFFIC CIRCLE IN PINEHURST TO NC 73. WIDEN TO MULTILANES.
ROLL 2 OF 2